



PROPOSED LOCATION FOR 1,200 SF CLASSROOM FACILITY
55'x55' AREA TO BE CLEARED
FFE = 8.0 FT
(NGVD 1929)

NOTE 1:

8" HDPE CLEANOUT W/12"x12"x6" CONCRETE APRON
INV. EL.=5.36

NOTE 2: TRAIL HAS BEEN HAND CLEARED AND IS NOT PART OF THE SCOPE OF WORK.

SITE DATA TABLE

CONCRETE SIDEWALK (IMPERVIOUS)	3573 SF
ASPHALT (IMPERVIOUS)	2749 SF
CLASSROOM FACILITY (IMPERVIOUS)	1200 SF
PAVERS (PERVIOUS)	4444 SF
GRAVEL (GEOWEB)	16084 SF
PROPOSED TRAIL (PERVIOUS)	89965 SF

18 FULL SIZE PARKING SPOTS
2 HANDICAP PARKING SPOTS
2 SCHOOL BUS PARKING SPOTS
22 PARKING SPOTS

LEGEND

	PROPOSED TRAIL LOCATION (N.I.C.)		CONCRETE SIDEWALK		ASPHALT PAVEMENT
	25' WETLAND BUFFER		GRAVEL DRIVE W/GEOWEB		GRASS PAVER
	EXISTING ASPHALT ROAD				

REV NO.	REVISION	DATE	DRAWN BY / EMP. NO.	CHECKED BY / D.P. NO.	WM APPROVED BY:	ACTIVITY	INITIALS/EMP. NO.	DATE
1	REVISED FOR THE RECORD	FEB 2009	JG/2031					

CLIENT: WALTON COUNTY TOURIST DEVELOPMENT COUNCIL
PROJECT: NATURE CENTER

DATE: MAY 2008
HORIZONTAL SCALE: 1" = 30'
VERTICAL SCALE: NA
SEC: TWP: RGE: 14 25 20W

TITLE: SITE PLAN
INDEX NUMBER: D-04186-034
PROJECT NUMBER: 04186-010-003
SHEET NUMBER: 5 OF 10